

# RACK GUARD SYSTEM®

## Installation Instructions

- Steel Rack Guards Prevent Items from Falling
- Available in Stock Widths from 7 to 12 Feet and Heights from 3 to 5 Feet
- Panels are Attached to Pallet Rack Systems Using Spacer Clips
- 8-gauge, 2" x 2" square Welded Wire Mesh Welded into Heavy Angle Iron Frames for Longevity and Dependability
- Inventory Visibility
- Polyurethane Yellow Finish



MODEL	H	W	WT
RGW0703	36"	7'	36.68
* RGW0803	36"	8'	41.12
RGW0903	36"	9'	45.55
RGW1003	36"	10'	49.98
RGW1203	36"	12'	58.75
RGW0704	48"	7'	44.32
* RGW0804	48"	8'	49.58
* RGW0904	48"	9'	54.83
* RGW1004	48"	10'	60.08
* RGW1204	48"	12'	70.49
RGW0705	60"	7'	51.96
* RGW0805	60"	8'	58.04
RGW0905	60"	9'	64.11
* RGW1005	60"	10'	70.19
* RGW1205	60"	12'	82.24

SPACER CLIPS		PRICE
* RC0000	FLUSH	\$5.59
* RC0400	4'	\$5.79
* RC0600	6'	\$5.93
RC0800	8'	\$6.06
RC1000	10'	\$6.19
RC1200	12'	\$6.33

Spacer Clips Required (4) Per Panel

\* HIGHLIGHTED AREAS ARE QUICK SHIP  
48 HOURS GUARANTEED OR WE PAY  
THE FREIGHT

NOTE: The Rack Guard using 10-gauge 1-1/2" diamond wire mesh is available upon request call: 800-438-5629.




Call 800-438-5629 or visit [www.wirewayhusky.com](http://www.wirewayhusky.com)


# RACK GUARD SYSTEM®

## Installation Instructions

Extension support for guards above Pallet Rack height.



Inside View  
Guards have pre-punched holes for bolting with carriage bolts (included).  
When putting guards flush together, line up Bolt Holes in center area.



### Specifications:

1. Rack Guard brackets, bolts and nuts required with each panel.
2. One Panel required for each Rack Bay (Panel is same length as Beam)
3. Construction-- 2" x 2" 8-gauge wire mesh, welded in 1-1/4" x 1-1/4" x 1/8" angle frame.
4. 1" x 3/8" carriage bolts
5. See inset for assembly



Flush Mount Bracket

Side view Standoff Bracket

